

# INFORMAL TENDER ADVERT

**NELSON MANDELA BAY MUNICIPALITY**  
BUDGET AND TREASURY DIRECTORATE  
PURCHASING AND STORES DIVISION

Tender Number: CSQ03265449  
Buyer: Witbooi, Mr AE [90000594]

Closing Date: 2026-04-23  
Closing Time: 11:00 A.M

Telephone : 041 506 7630

REFER ALL ENQUIRIES TO THE BUYER

ITEM	QUANTITY	UNIT	KEY WORD	DESCRIPTION	REQUISITION
1	1.00	LOT	BUILDING RENOVATIONS	<p>Tenders are invited for Building Renovations work as per specifications and returnable pricing schedule available on our NMBM on-line tender portal</p> <p>Compulsory site meeting to be held:</p> <p>Venue: Allan Hendricks Complex 201 Durban Rd Korsten Gqeberha</p> <p>Date: 16 April 2026 Time: 10h30am</p> <p>Tenderers will be further evaluated only if they meet the minimum requirement as per specifications stated below: Brand name /Delivery Period of item must be stated on informal tender quote with submission on electronic system. Brochure /sample of item may be requested from short listed tenderers after closing of Tender and to be provide within 72 hours of the request to provide. Failure to meet the minimum requirements will deem the tender non-responsive.</p> <p>For further information please contact Mr F Mamatt @ 041 994 1173.</p>	AA168374

## THE FOLLOWING CONDITIONS APPLY TO THIS INFORMAL TENDER

- BEFORE COMPLETING THIS FORM, SERVICE PROVIDERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF SPECIFIC GOALS, AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATION OF 2022 THE 80/20 SYSTEM APPLIES TO THIS TENDER.
- Acceptance of this tender submission is subject to the General Conditions of Tender and Conditions of Purchase
- Acceptance of this tender is subject to successful registration on the Nelson Mandela Bay Supplier Database.
- For further information to register, please call Compliance Section @ 041 506 3274
- Failure to comply with these conditions may invalidate your tender submission.
- All tender prices should be valid for a minimum period of thirty (30) days from date of tender.
- ALL TENDER RESPONSES SHOULD BE COMPLETED ONLINE AND NO FAX SUBMISSION WILL BE ACCEPTED BY SUPPLY CHAIN UNIT.

**INFORMAL TENDER CSQ03265449**

**SCOPE OF WORK AND SPECIFICATION**

**1. Purpose**

Repairs and maintenance on exterior part of the building, two units and ablution facilities to Allen Hendricks Old Age Homes.

**2. Background**

To create a safe and healthy environment for the elderly.

**3. Scope of work**

Description of work	Removing of unwanted vegetation, damaged concrete and casting of new concrete slabs to the affected areas
---------------------	---

**Conditions of Informal Tender**

1. Informal tender is open for all CIDB (GB1.) and higher contractors.
  - 1.1 A copy of the Active CIDB registration or Registration Number to be submitted as a returnable schedule.
  - 1.2 Verification of Active CIDB registration will be done on the day of scoring
2. Orders will be issued based on the CIDB grading per year.
3. Tender conditions to be that of the CIDB and GP GCC 2010
4. Please take note that should you not complete the work within the delivery period, the NMBM reserves the right to cancel the Order in terms of clause 23.2 of the GP GCC 2010.
5. Please further take note that Contingency has been allowed for in the Returnable Pricing Schedule and as per clause 18 and 25 of the GP GCC 2010. Authorisation must be received from the Project Manager prior to work being performed on site. Take note that this is a percentage of the amount to do the works for unexpected / unforeseen events, which gets deducted from the offered price if not required.
6. The rates supplied by the Service provider are deemed to be all inclusive. Including the provision of security where necessary to guard the material delivered on site, until the project is handed back over to NMBM.

**Note: NMBM is not responsible for lost or stolen items or materials on site that belong to the Contractor. The Contractor is solely responsible for the security of its belongings.**

7. A Health & Safety file is a requirement for this informal tender.
8. **Provide proof of trade test certificate**/CETA/BIBC card or completed apprenticeship contract relevant to the scope of works. **This is a returnable document.**
9. Contractor to confirm price and delivery date submitted before order is approved.
10. The contractor must, within 3 days of receiving the letter of appointment or order number from SCM, submit a scheduled programme with clear commencement and completion. Consider the delivery date submitted on the offer.
11. Should a contractor fail to comply with the specification or schedule programme submitted, the PM will on behalf of the client give notice of its intention to terminate the order. If the contractor does not remedy the non-performance, the **order will be terminated** within 3 working days.
12. Rubble to be removed daily from site.
13. **No** Part Payment will be made in this contract. Service providers to ensure that there is adequate funding to do the works.
14. Working hours are to be weekdays between 08H00 and 16H00. After hours or non-working hours and weekends to be approved by Project Manager. No additional labour to be incurred by NMBM on work done after hours
15. The service provider is to use local ward-based labour. Further take note that, for projects that are R 30 000-00 and above, the service provider is to complete EPWP certificates and supply all necessary documentation when submitting an invoice. For more information, contact Brian Mabusela on 0415061093
16. Service provider to ensure that all staff sign attendance register daily.
17. **COMPULSORY SITE MEETING**  
Venue: Allan Hendricks Complex  
201 Durban Rd  
Korsten  
Gqeberha  
Date: 16 April 2026  
Time: 10h30am

**Functionality****OLD AGE HOME****External walls 467.4m<sup>2</sup>**

- Prepare the surfaces by washing down using a water high pressure cleaner and allow the surfaces to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks & cervices shall be opened, filled with a suitable filler and finished smooth. Uproot ingrown plants from the wall façade.
- Supply and apply coat of quickset epoxy/ masonry primer/sealer for adhesion and moisture protection where necessary.
- Supply and apply two coats superior quality acrylic emulsion Dulux/Plascon paint or elastomeric coating for durability and UV resistance for exterior use to match the existing or equivalent.

**Roof and rainwater goods**

- Clean and wash the roof surfaces to remove dirt, moss, algae and debris. Ensure compliance with health, safety and environmental regulations, especially for containing materials. Prepare by washing down using low-pressure water spray and apply approved boicide or detergent for moss/algae removal, collect runoff water safely and dispose of according to hazardous waste guidelines. - **487.2m<sup>2</sup>**
- Prepare sprockets/rafters by inspecting all sprockets/rafters for damage or rot, clean surfaces to remove dust, dirt, and loose particles, sand surface to smooth rough areas ad ensure paint adhesion. Supply and apply one coat of wood primer and two coats of high-quality exterior paint (UV-resistant and weatherproof)- **24m<sup>2</sup>**
- Prepare by cleaning, scape off loose paint, sand surfaces fascia boards and gables. Supply and apply one coat of primer suitable for timber or fibre cement surfaces. Supply and apply two coats of high-quality exterior paint (UV and weather-resistant) ensure even coverage and proper drying time between coats. - **33m<sup>2</sup>**
- Supply and replace 2 PVC gutters and 8 downpipes, matching brackets, stop ends, outlets, and joiners. Make sure correct slope for water flow to downpipes and secure gutters to fascia boards using corrosion-resistant fasteners. – **Item**

**ROOM 78, 88 & 84**

- Supply and replace 6.4mmx1200x3000mm RhinoBoard ceiling, measure the length of the ceiling and deduct 10mm to allow for expansion. Use a chalk line and utility knife to cut the RhinoBoard sheets to size. Snap the board

along the cut line and smooth the edges with a rasp. Fix the boards with screws at 150mm intervals. - **78m<sup>2</sup>**

- Supply and replace rhino cornice, apply a generous amount of cornice adhesive to the back of the cornice. Press the cornice firmly into place along the marked lines on the wall and ceiling. - **84m**
- Supply and apply a coat of primer to the ceiling using a roller for large areas and a brush for edges and corners. Allow the primer to dry completely according to the manufacturer's instructions. Supply and apply double coats of Plascon PVA Paint in even strokes, starting from one corner and working your way across the rhino board ceiling. – **84.3m<sup>2</sup>**
- Supply and lay PVC tiling multi-Flor Avellino 613M Vinyl - Havanna Oak (2000mm x Per Meter) or equivalent. Supply and apply a layer of adhesive to a section of the floor using a notched trowel. Follow the adhesive manufacturer's instructions for drying time before placing the tiles. Once all tiles are in place, use a roller to press them firmly into the adhesive and ensure a good bond. Roll the entire floor, paying special attention to the edges and corners. - **78m<sup>2</sup>**
- Supply and install laminated Skirting 8.3mm Cherry 15x80x2400mm. Supply and apply a suitable adhesive to the back of the skirting board in a wavy line to ensure even coverage. Press the skirting firmly against the wall and floor, holding it in place for a few seconds to allow the adhesive to bond. – **84m**
- Prepare internal walls by scrape off any damaged or flaking paint from the affected area. Sand down and fill in cracks using crack filler, Supply coat of primer and apply two coats of Plascon/ Double Velvet wall paint or equally approved by the project manager. –**204.99m<sup>2</sup>**
- Remove the existing doors and frames old adhesive. door frame, ensuring all hardware and fixtures are safely disconnected and removed. -**6no**
- Supply and fit 2 new Swartland Kayo 6 Panel Colonial Mixed Timber Exterior Door 813 x 2032 mm or equally approved by the Project Manager including stainless steel hinges, lever handles with a privacy lock, and a rubber-tipped door stopper. -**6no**
- Use a scraper to remove all old paint from the steel window frames. Sand the frames with 80 grit sandpaper to remove existing rust and create a smooth surface for painting. -**16.35m<sup>2</sup>**
- Supply & apply the first coat of Plascon Door & Trim Enamel White or a similar high-quality paint suitable for metal surfaces. After the first coat has

dried as per the manufacturer's instructions, apply a second coat to ensure complete coverage and durability. --**117m<sup>2</sup>**

- Supply and replace floor cupboards 2000 x 400 x 900 mm high with 32 mm thick PG Bison Postform Top Black Slate with 2-3mm bevel on surface edge, 'PG Bison' 16 mm High Gloss Melamine super white double and single hinged doors and bottom and 16 mm Melamine dividing framework, shelves, sides, back and drawers. Wall cupboards 2000 x 400 x 700 mm high 'PG Binson' 16 mm High Gloss Melamine super white double and single hinged doors and 16 mm Melamine dividing framework, shelves, back and sides.
- Supply and replace Rectangular Sink — 365 mm x 318 mm (≈ 14" x 12.5") and a tap with its plumbing accessories, fittings. -**3No**

### **ELECTRICAL WORK**

#### **Supply and install:**

- 6x63A Double Pole Circuit Breaker
- 6x20A Single Pole Circuit Breaker
- 3x40A Double Pole Circuit Breaker
- 12x Single Lever Switches
- 6x Double Socket Outlets
- 3x100m twin& Earth 2,5mm<sup>2</sup>
- 3x100m twin& Earth 1.5mm<sup>2</sup>
- 3x 100W LED Flood Light
- 6x Outside Lights
- 3x63A Earth Leakage C.B

### **ABLUTION**

- Supply and install RhinoBoard ceiling trap doors 600mmx600m. – **4no**
- Supply and replace rhino cornice, apply a generous amount of cornice adhesive to the back of the cornice. Press the cornice firmly into place along the marked lines on the wall and ceiling and paint to match the existing. - **62m**
- Supply and apply a coat of primer to the ceiling using a roller for large areas and a brush for edges and corners. Allow the primer to dry completely according to the manufacturer's instructions. Supply and apply two coats of PVA Paint to the ceiling- **120m<sup>2</sup>**
- Prepare internal walls by scrape off any damaged or flaking paint from the affected area. Fix the damaged wall by bricking up and plaster make neat. Sand down and fill in cracks using crack filler, Supply coat of primer and apply two coats of Plascon Double Velvet wall paint or equally approved by the project manager. -**204m<sup>2</sup>**

- Use a scraper to remove all old paint from the steel window frames. Sand the frames with 80 grit sandpaper to remove existing rust and create a smooth surface for painting. – 39m<sup>2</sup>
- Supply & apply the first coat of Plascon Door & Trim Enamel White or a similar high-quality paint suitable for metal surfaces. After the first coat has dried as per the manufacturer's instructions, apply a second coat to ensure complete coverage and durability on the doors. – 39m<sup>2</sup>
- Clean 8 surface doors of any old finishes or debris. Supply & apply the two coats of Plascon Enamel or equally approved by Project Manager. Allow each coat to dry completely before applying the next. -8no
- Remove the old, damaged flooring and Prepare floor by scrapping and sand off all the glue off & patch all holes to receive a new tiling. Supply and replace A Grade Nonslip Porcelain tile (600 x 600mm) or equivalent. Supply the material- tile grout, tile spacers, tile adhesive (thinset) and Tile door trim. -90m<sup>2</sup>
- Remove the broken pan of glass make it neat and install a new pan to match the existing. -3m<sup>2</sup>
- Install spikes all around the existing anti-climb fence. -130m

#### **HANDRAIL 100m**

- Prepare the handrail by scraping off the existing and treating the wood. Supply and apply the wooden weather resistant paint to the handrails.

**Leave site clean on completion. Remove and cart away all rubble.**

#### **Requirements**

##### **General**

- A Health & Safety file is a requirement for this informal tender.
- **Provide proof of trade test certificate**/CETA/BIBC card or completed apprenticeship contract relevant to the scope of works. **This is a returnable document.**
- Contractor to confirm price and delivery date submitted before order is approved.
- The contractor must, within 3 days of receiving the letter of appointment or order number from SCM, submit a scheduled programme with clear commencement and completion.
- Should a contractor fail to comply with the specification or schedule programme submitted, the PM will on behalf of the client give notice of its intention to terminate the order. If the contractor does not remedy the non-performance, the **order will be terminated** within 3 working days.
- Rubble to be removed daily from site.
- **No** Part Payment will be made in this contract. Service providers to ensure that there is adequate funding to do the works.

	<ul style="list-style-type: none"> <li>○ Working hours are to be weekdays between 08H00 and 16H00. After hours or non- working hours and weekends to be approved by Project Manager. No additional labour to be incurred by NMBM on work done after hours</li> <li>○ The service provider is to use local ward-based labour. Further take note that, for projects that are R 30 000-00 and above, the service provider is to complete EPWP certificates and supply all necessary documentation when submitting an invoice. For more information, contact Ms N Nikelo on 0415061133</li> <li>○ Service provider to ensure that all staff sign attendance register daily.</li> <li>○ <b>SITE MEETING IS COMPULSORY.</b> Venue: Allan Hendricks Complex 201 Durban Rd Korsten Gqeberha Date: 16 April 2026 Time: 10h30am</li> <li>○ Returnable Schedule with the Returnable as per SCM requirements</li> </ul>
--	---

**Minimum Requirements**

- Provide proof of trade certificates Painter, Carpentry, electrical Certificate. Completed apprentice, SETA training.
- Provide CIBD1 (GB) and higher contractors.
- Provide fully priced returnable as per SCM requirement.

**Above must be up-loaded before Close of Informal Tender date and time to avoid been NON-RESPONSIVE.**

**4. Evaluation Process**

- a) It is important to note that any proposal that does not conform fully to the above will be disqualified and will not be considered.
- b) Secondly the proposal will be evaluated according to the tender evaluation process applicable to the NMBM.

**5. Disputes**

Disputes must be settled by means of mutual consultation, mediation (with or without legal representation) or when unsuccessful, in a South African Court of Law

**6. Queries**

Queries can be directed to:

Project Manager: Feisel Mamatt  
 Email: fmamatt@mandelametro.gov.za  
 Tel: (041) 994 1173  
 Cell: 076 832 8664

**7. Disputes**

Disputes must be settled by means of mutual consultation, mediation (with or without legal representation) or when unsuccessful, in a South African Court of LaW.

## Corporate Services

**INFORMAL TENDER CSQ03265449**

### RETURNABLE PRICE SCHEDULE

SPECIFICATION FOR OLD AGE HOME

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.	<b><u>OLD AGE HOME</u></b> <b><u>External walls 51m<sup>2</sup></u></b>				
1A	Prepare the surfaces by washing down using a water high pressure cleaner and allow the surfaces to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks & cervices shall be opened, filled with a suitable filler and finished smooth. Uproot ingrown plants from the wall façade.	M <sup>2</sup>	467.4	R	R
1B	Supply and apply coat of quickset epoxy/ masonry primer/sealer for adhesion and moisture protection where necessary. Supply and apply two coats superior quality acrylic emulsion Dulux/Plascon paint or elastomeric coating for durability and UV resistance for exterior use to match the existing or equivalent.	M <sup>2</sup>	390	R	R
2	<b><u>Roof and rainwater goods</u></b>				
2A	Clean and wash the roof surfaces to remove dirt, moss, algae and debris. Ensure compliance with health, safety and environmental regulations, especially for containing materials. Prepare by washing down using low-pressure water spray and apply approved boicide or detergent for moss/algae removal, collect runoff water	M <sup>2</sup>	487.2	R	R

Supplier Name:.....

	safely and dispose of according to hazardous waste guidelines.				
2B	Prepare sprockets/rafters by inspecting all sprockets/rafters for damage or rot, clean surfaces to remove dust, dirt, and loose particles, sand surface to smooth rough areas and ensure paint adhesion. Supply and apply one coat of wood primer and two coats of high-quality exterior paint (UV-resistant and weatherproof).	M <sup>2</sup>	24	R	R
2C	Prepare by cleaning, scrape off loose paint, sand surfaces fascia boards and gables. Supply and apply one coat of primer suitable for timber or fibre cement surfaces. Supply and apply two coats of high-quality exterior paint (UV and weather-resistant) ensure even coverage and proper drying time between coats.	M <sup>2</sup>	33	R	R
2D	Supply and replace PVC gutters and 8 downpipes, matching brackets, stop ends, outlets, and joiners. Make sure correct slope for water flow to downpipes and secure gutters to fascia boards using corrosion-resistant fasteners.	ITEM	2	R	R
3	<b><u>ROOM 78, 88, &amp; 84</u></b>				
3A	Supply and replace 6.4mmx1200x3000mm RhinoBoard ceiling, measure the length of the ceiling and deduct 10mm to allow for expansion. Use a chalk line and utility knife to cut the RhinoBoard sheets to size. Snap the board along the cut line and smooth the edges with a rasp. Fix the boards with screws at 150mm intervals.	M <sup>2</sup>	78	R	R
3B	Supply and replace rhino cornice, apply a generous amount of cornice adhesive to the back of the cornice. Press the cornice firmly into place along the marked lines on the wall and ceiling.	M	84	R	R
3C	Supply and apply a coat of primer to the ceiling using a roller for large areas and a	M <sup>2</sup>	84.3	R	R

**Supplier Name:**.....

	brush for edges and corners. Allow the primer to dry completely according to the manufacturer's instructions. Supply and apply double coats of Plascon PVA Paint in even strokes, starting from one corner and working your way across the rhino board ceiling.				
3D	Supply and lay PVC tiling multi-Flor Avellino 613M Vinyl - Havanna Oak (2000mm x Per Meter) or equivalent. Supply and apply a layer of adhesive to a section of the floor using a notched trowel. Follow the adhesive manufacturer's instructions for drying time before placing the tiles. Once all tiles are in place, use a roller to press them firmly into the adhesive and ensure a good bond. Roll the entire floor, paying special attention to the edges and corners.	M <sup>2</sup>	78	R	R
3E	Supply and replace laminated Skirting 8.3mm Cherry 15x80x2400mm. Supply and apply a suitable adhesive to the back of the skirting board in a wavy line to ensure even coverage. Press the skirting firmly against the wall and floor, holding it in place for a few seconds to allow the adhesive to bond.	M	84	R	R
3F	Prepare internal walls by scrape off any damaged or flaking paint from the affected area. Sand down and fill in cracks using crack filler, Supply coat of primer and apply two coats of Plascon/ Double Velvet wall paint or equally approved by the project manager.	M <sup>2</sup>	204.99	R	R
3G	Remove the existing doors and frames old adhesive. Door frame, ensuring all hardware and fixtures are safely disconnected and removed. Supply and fit 2 new Swartland Kayo 6 Panel Colonial Mixed Timber Exterior Door 813 x 2032 mm or equally approved by the Project Manager including stainless steel hinges, lever handles with a privacy lock, and a rubber-tipped door stopper.	No	6	R	R
3H	Use a scraper to remove all old paint from the steel window frames. Sand the frames with 80 grit sandpaper to remove existing rust and create a smooth surface for	M <sup>2</sup>	16.35	R	R

Supplier Name:.....

	painting. Supply & apply the first coat of Plascon Door & Trim Enamel White or a similar high-quality paint suitable for metal surfaces. After the first coat has dried as per the manufacturer's instructions, apply a second coat to ensure complete coverage and durability.				
3I	Supply and replace floor cupboards 2000 x 400 x 900 mm high with 32 mm thick PG Bison Postform Top Black Slate with 2-3mm bevel on surface edge, 'PG Bison' 16 mm High Gloss Melamine super white double and single hinged doors and bottom and 16 mm Melamine dividing framework, shelves, sides, back and drawers. Wall cupboards 2000 x 400 x 700 mm high 'PG Binson' 16 mm High Gloss Melamine super white double and single hinged doors and 16 mm Melamine dividing framework, shelves, back and sides.	No	3	R	R
3J	Supply and replace Rectangular Sink (365 mm x 318 mm) and a sink tap with its plumbing accessories, fittings.	No	3		
	<b><u>ELECTRICAL</u></b>				
	<p>1 <u>Supply and install:</u></p> <ul style="list-style-type: none"> <li>• 6x63A Double Pole Circuit Breaker</li> <li>• 6x20A Sindle Pole Circuit Breaker</li> <li>• 3x40A Double Pole Circuit Breaker</li> <li>• 12x Single Lever Switches</li> <li>• 6x Double Socket Outlets</li> <li>• 3x100m twin&amp; Earth 2,5mm<sup>2</sup></li> <li>• 3x100m twin&amp; Earth 1.5mm<sup>2</sup></li> <li>• 3x 100W LED Flood Light</li> <li>• 6x Outside Lights</li> <li>• 3x63A Earth Leakage C.B</li> </ul>	ITEM	1	R	R
4	<b><u>ABLUTION</u></b>				
4A	Supply and install RhinoBoard ceiling trap doors 600mmx600mm.	No	4	R	R
4B	Supply and replace rhino cornice, apply a generous amount of cornice adhesive to the back of the cornice. Press the cornice firmly into place along the marked lines on the wall and ceiling.	M	62	R	R

**Supplier Name:**.....

4C	Supply and apply a coat of primer to the ceiling using a roller for large areas and a brush for edges and corners. Allow the primer to dry completely according to the manufacturer's instructions. Supply and apply two coats of PVA Paint to the ceiling.	M <sup>2</sup>	120	R	R
4D	Prepare internal walls by scrape off any damaged or flaking paint from the affected area. Sand down and fill in cracks using crack filler, Supply coat of primer and apply two coats of Plascon Double Velvet wall paint or equally approved by the project manager.	M <sup>2</sup>	204	R	R
4E	Use a scraper to remove all old paint from the steel window frames. Sand the frames with 80 grit sandpaper to remove existing rust and create a smooth surface for painting. Supply & apply the first coat of Plascon Door & Trim Enamel White or a similar high-quality paint suitable for metal surfaces. After the first coat has dried as per the manufacturer's instructions, apply a second coat to ensure complete coverage and durability on the doors.	M <sup>2</sup>	39	R	R
4F	Clean 4 surface doors of any old finishes or debris. Supply & apply the two coats of Plascon Enamel or equally approved by Project Manager. Allow each coat to dry completely before applying the next.	No	4	R	R
4G	Remove the old, damaged flooring and Prepare floor by scrapping and sand off all the glue off & patch all holes to receive a new tiling. Supply and replace A Grade Nonslip Porcelain tile (600 x 600mm) or equivalent. Supply the material- tile grout, tile spacers, tile adhesive (thinset) and Tile door trim.	M <sup>2</sup>	90	R	R
5	Install spikes all around the existing anti-climb fence.	No	130	R	R
6	<b><u>HANDRAIL</u></b>				



**Supplier Name:.....**

6A	Prepare the handrail by scraping off the existing and treating the wood. Supply and apply the Plascon wooden weather resistant paint or equivalent to the handrails. x 3 coats of which the first coat to be thinned out to better penetration of the wood and protection.	M	100	R	R
	<b>Subtotal</b>				<b>R</b>
	<b>GENERAL</b>				
	Contingency 10%				R
	Health and Safety file				R
			<b>SUBTOTAL</b>	R	
			<b>ADD 15% VAT</b>	R	
			<b>TOTAL</b>	R	

**NB: FAILING TO ATTEND SITE MEETING & ATTACH RETURNABLE DOCUMENTS / MINIMUM REQUIREMENTS AS REQUESTED BEFORE CLOSING DATE & TIME OF INFORMAL TENDER WILL RESULT IN DISQUALIFICATION.**

Supplier Name: -.....

Contact Name:-.....Tel No.....

Signature:-.....Date:-.....

**NB: THIS DOCUMENT MUST BE COMPLETED AND LOADED ONTO ON-LINE SUBMISSION AS ATTACHMENT BEFORE THE CLOSE OF TENDER DATE & TIME**

**NB!! Price/s submitted must include VAT, weather you are VAT registered or not, in line with the PPPFA of 2022 and section 64 of the VAT Act, No 89 of 1991**

